Name of work:- Construction of drain in 2nd & 3rd main Rly extension in ward-18 (4)

DTS FOR APPROVAL

item_code	description	uom_name	quantity	rate
18.17	Dismantling of existing strutures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metrs complete as per specifications. i) Lime / Cement Concrete. I. By Manual Means : A. Lime Concrete, cement concrete grade M-10 and below. MORTH Specification No.202 Page No.147. I No.18.17 PWDSR - 2013-14	Cum	97.20	253.80
2.4	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in ordinary soil not exceeding 1.5 m. in depth including sressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications. specification No. KBS 2.1 (b) / 2.3.5. P No.5 I No. 2.4 PWDSR - 2013-14	Cum	102.00	151.70
4.3	Providing and laying in position plain cement concrete of mix M 75 with OPC @ 180 kgs using 40mm and down size graded granite metal CA @ 0.85 cum and FA @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM machinery, curing complete as per specifications. Specification No.KBS 4.1,4.2 P No. 12. I no 4.3 PWDSR - 2013-14	Cum	44.70	4290.80
5.12	Providing and constructing grabute / trap / basalt size stone masonry in superstructure with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, scaffolding, curing complete as per specifications. KBS 5.1.13 Page No.26. I No.5.12 PWDSR - 2013-14	Cum	100.86	4423.70
4.6	Providing and laying in position plain cement concrete of nominal mix M 15 with cement @ 240 kgs using 20mm and down size graded granite metal, CA @ 0.878 cum FA @ 0.459 cum and machine mixed, concrete laid in layers not exceeding 15 cms. Thick, well compacted in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 Page No.12. I N0.4.6 PWDSR - 2013-14	Cum	16.83	4779.00

15.3	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, incluing cost of materials, labor, curing complete as per specifications. Page No.122. I No.15.3 PWDSR - 2013-14	Sqm	224.40	79.90
4.11	Providing and laying in position reinforced cement concrete of nominal mix M 20 with OPC @ 320 kgs with 20mm and down size graded granite metal CA @ 0.878 cum and FA @ 0.459 cum machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, columns, piers, abutments, pillars, posts, sturts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. (excluding cost of steel, fabrication and plastering) Specification No. KBS 4.1, 4.6 Page No.12. I No.4.11 PWDSR - 2013-14	Cum	16.43	5639.00
1	Providing and laying position reinforced cement concrete covering slabs madeout of mix 1:1.50:3 with 20mm and down size granite metal mixed concrete laid in layers not exceeding 15cms vibrated including cost of materials, labor curing providing and laying in position including transportation complete as per specification.			
2	For 10 cms thickness slab	Sqm	270.00	1427.00
3	For 20 cms thickness slab	Sqm	21.00	2102.12
5.29.1	Providing and fixing Pre cast solid concrete kerb stones made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., complete. of size 450 x 200 x 400 mm P 24 I NO.5.29.1 PWDSR - 2013-14	Nos	445.00	316.45
	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plasered concrete surfaces, with materials, labour compete as per specifications. Specification No.KRBS 800.3 MORT & H Specification No.800. P No. 195 I no 24.1 PWDSR - 2013-14	Sqm	54.00	51.84
	Charges of Haulage Excluding Loading and Unloading MORTH Chapter 1 (Lead chart enclosed)	Cum	180.00	94.82

5639.00 C2

ಆಯುಕ್ತರವರ ಸುತ್ತೋಲೆ ಸಂಖ್ಯೆ:
(ಜಾ.ಮತ್ತು.ಪಿ.ಪಿ.ಇ.ಡಿ) / ಪಿ.ಆ
12-13 ದಿನಾಂಕ 19-04-2013 ರ
ಚನೆಗಳಂತೆ ಕ್ರಮವಹಿಸುವುದು ಹಾ
ಜು ಪಟ್ಟಿಯಲ್ಲಿನ ವಿಶಿಷ್ಟ ವಿವರಣೆ
IFICATION) ಪರಿಮಾಣಗಳನ್ನು (QUANTITY)
ಹಾಗೂ ದರಗಳನ್ನು (RATES)
ಮತ್ತು ಮೇ. ಪರಿಶೀಲಿಸಿಕೊಳ್ಳತಕ್ಕದ್ದು.
ಸದು ಟೆಂಡರ್ ಪೆಡ್ಯೂಲನ್ನು ತಿದ್ದುಪಡಿ ಮಾಡಿದಂತೆ
ಪಡೆದಾರರಿಗೆ ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ: 1 (ಒಂದು)

ಅ.ತಾ./ಮು.ಅ.(ಪೂರ್ವ)

Executive Engineer,
Hebbal Division,
Bruhat Bangalore Mahanagara Palike